

“Another successful project by TecGates Engineering”

Coal Handling System for 1X1000MW Manjung Coal Fired Power Plant

Material Handled : Coal (Manjung 4)
Delivery Time : 39 months

TOTAL ENGINEERING AND EQUIPMENT SUPPLY

- 1) Conveyor System : 6 units at 3800 TPH & 8 units at 1400 TPH, 4 km total length
- 2) Stacker / Reclaimer : 2 units Stacking – 3800 TPH / Reclaiming – 1400 TPH
- 3) Tripper Car : 2 units, 1400 TPH
- 4) Crushing Station : 1400 TPH, output size <50mm
- 5) Screen (Banana type) : 1400 TPH (Separation size : +50m, -50m)
- 6) Dust Suppressant : Dry fog system for transfer tower and stock yard
- 7) Dust Collection : At Screen house / Bunker floor and Tripper car



 **TecGates**
TECGATES ENGINEERING (M) SDN. BHD. (254230-#)

For more information, please contact

+603 2721 4970



www.tecgates.com.my